



**PRICES SUBJECT TO CHANGE AT
TIME OF CONTRACT DUE TO
VOLATILITY IN THE LUMBER**

Prepared For:

Steven Bloyed
North Brunswick Twp
45 Quarry Lane
North Brunswick, NJ 08902

**QUOTE NUMBER:
PQS-688794-002**

Page: 1 of 1
Quote Date: 10/8/2025
Quote By: Samantha
Customer ID: 688794

Phones: Home: (732) 439-6970 • Work: (732) 297-1134 • Mobile: (732) 995-1556

Building

Dimensions: **50'W x 80'L x 16'4"H**
3 ply 2 x 6 glu-laminated, poles 8' on center
Siding: 28 Gauge Frontier Panel 50 Year Warranty
Roofing: 27 Gauge Frontier Panel 50 Year Warranty
50' Standard Trusses, 4' on center, 4/12 pitch, snow load by code and design

Openings

(3) 14'W x 14'H Residential Premium Raised Short Panel Insulated, 15" track, Placement: eave
(1) Entry Door 3068 inswing 6-panel RH Fiberglass Insulated PRIMED

Overhangs

Eaves Overhang: Flush, Gables Overhang: Flush

Miscellaneous

80 ft, Universal Ridge Vent
2 x 6 Skirtboard .60 Treated with barrier tape

Additional

****Prevailing Wage****

Total for above building erected on your level, compacted site: \$94,127

Additional Options

Openings

(1) 14'W x 14'H Residential Premium Raised Short Panel **Insulated**, 15" track, Placement: eave \$6,731

Overhangs

Eaves Overhang: OH 1' \$3,280
Gables Overhang: OH 1' \$1,872

Miscellaneous

Trash Removal, If Needed \$350
Engineered Sealed Blueprints (If Required By Township/County) \$750
Non Stamped Blueprints Free

Additional Materials

-Pioneer to layout and cut 2' x 2' area for post positions in existing (concrete/asphalt). Customer is responsible for cutting holes in pad for Pioneer to drill footers. Pioneer is not responsible for damage caused to existing (concrete/asphalt) during construction of building \$3,000

Ask about our Excavation services!

716 South Route 183, Schuylkill Haven, PA 17972 • Phone: 888-448-2505 • Fax: 888-448-2515 • www.ppb1.com
PA: PA001577 NJ: 13VH00797400 MD: 121132 DE: 2001105056 VA: 2705128610 WV: WV043315 NY: 24-64R4T-CR